

KANSAS

M
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1972 3-17-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Misco Supply Co.

Complete Address 257 N Broadway Wichita, Ks

Lease Name Koehn-Schmidt Well No. 1

Location SW/SW/NE Sec. 28 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5060

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Comstock Pipe Pulling Co. Inc.

Address Stafford, Ks License No. 490

Operation Completed: Hour 1:00 PM Day 15 Month 3 Year 1972

The above well was plugged as follows:

373 ft 8 5/8 surface pipe cemented with 250 sacks. 5055 ft 5 1/2 long
string cemented with 100 sacks. Top perf. 4940 ft. Push plug to
4500 ft. Sand back to 4450 ft. Pulled 2800 ft 5 1/2. Set 10 ft rock
bridge at 220 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *L. Russell B. ...*
Well Plugging Supervisor

INVOICED

DATE 3-17-72

INV. NO. 5366-11