

KANSAS

Form CP-3
Rev. 6-4-68

X STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Misco Supply Co.

Complete Address 257 N Broadway Wichita, Ks

Lease Name V.H. Koehn Well No. 5

Location C NW/SE Sec. 28 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5050

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 5:00 PM Day 29 Month 9 Year 1971

The above well was plugged as follows:
378 ft 8 5/8 surface pipe cemented with 250 sacks. 5049 ft 5 1/2 long
string cemented with 125 sacks. Open hole. Sand back to 4900 ft,
5 sacks cement with bailer. Pulled 2900 ft 5 1/2. Set 20 ft rock bridge
at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell B. Bickman
Well Plugging Supervisor

DATE 10-1-71

INV. NO. 4401-W