

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Misco Supply Co.

Complete Address 257 N. Broadway Wichita, Ks

Lease Name Koehn 10 Well No. 8

Location C SE/SW Sec. 28 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5080

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Ralph Comstock Pipe Pulling Co.

Address Stafford, Ks License No. 490

Operation Completed: Hour 9:30 AM Day 11 Month 3 Year 1972

The above well was plugged as follows:

401 ft 8 5/8 surface pipe cemented with 250 sacks. 5078 ft 5 1/2 long  
string cemented with 125 sacks. Top perf. 4954 ft. Push plug to  
4500 ft. Sand back to 4450 ft, 5 sacks cement with bailer. Pulled  
3700 ft 5 1/2. Set 10 ft rock bridge at 220 ft. Fill hole with 3 yds  
redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed [Signature]  
Well Plugging Supervisor

INVOICED

DATE 3/13/72

INV. NO. 5333-U