

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Misco Supply Co.

Complete Address 257 N Broadway Wichita, Ks

Lease Name V.H. Koehn Well No. 11

Location C SW/NW Sec. 28 Twp. 29 Rge. 18 (E) W

County Kiowa Total Depth 5060

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Comstock Pipe Pulling Inc.

Address Stafford, Ks License No. 490

Operation Completed: Hour 9:00 AM Day 22 Month 3 Year 1972

The above well was plugged as follows:

412 ft 8 5/8 surface pipe cemented with 250 sacks. 5060 ft 5 1/2 long
string cemented with 125 sacks. Top perf. 4954 ft. Push plug to
4500 ft, sand & 5 sacks cement with bailer. Pulled 3300 ft 5 1/2. Set
10 ft rock bridge at 220 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Russell B. Bickerton*
Well Plugging Supervisor

INVOICED

DATE 3-24-72

INV. NO. 5411-11