

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Misco Supply Co.

Complete Address 257 N Broadway Wichita, Ks

Lease Name Mary Schmidt Well No. 1

Location C SW/NE Sec. 28 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5085

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 1:00 PM Day 29 Month 9 Year 1971

The above well was plugged as follows:
368 ft 8 5/8 surface pipe cemented with 250 sacks. 5085 ft 5 1/2 long
string cemented with 125 sacks. Top perf. 4997 ft. Sand back to
4950 ft, 5 sacks cement with bailer. Pulled 3025 ft 5 1/2. Set 20 ft
rock bridge at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10-1-71
INV. NO. 4404-W