

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 10 1967

CONSERVATION DIVISION  
Wichita, Kansas

4-10-1967

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued March 31, 1967.

Operator's Full Name Amarillo Natural Gas Compnay

Complete Address: Box 1257, Liberal, Kansas

Lease Name Hageman Well No. # 4

Location SW NE NE Sec. 15 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4525'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Sargent Casing Pulling Srevice

Address: 121 West Nineth, Liberal, Kansas License No. 511

Operation Completed: Hour 4:30PM Day 7th Month April Year 1967

The Above well was plugged as follows:

332' of 8 5/8" surface pipe, cemented with 225 sacks. 4525' of 5 1/2" long  
string, cemented with 150 sacks. Top perferation 4495'. 15 sacks of cement  
was pumped on bottom, the plug stopped at 2470', bringing the top of the  
to 2470'. 2068' of 5 1/2" long string was recovered from the hole. 20 sacks of  
cement was pumped on top of the Indian Cave Sand at 1735'. Hole was full of  
mud. Pipe was pulled up to 375', and 10 sacks of Gel-Mud was plumped at 375',  
through 5 1/2" swage. Pipe was pulled up to 250', and 30 sacks of cement was  
pumped, through 5 1/2" swage at 250'. 10 sacks of cement from fluid at 30' to  
the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/11/67

INV. NO. 5029-W