

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1962

CONSERVATION DIVISION
Wichita, Kansas

7-19-1962

Operator's Full Name Anschutz Oil Co., Inc.

Complete Address: 350 Denver Hilton Office Building, Denver, Colo.

Lease Name Hageman Well No. 3

Location SW NE NW Sec. 15 Twp. 29 Rge. 9 (E) (W) X

County Kingman Total Depth 4521'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Central Pipe Pulling Co.

Address: 1416 Coolidge, Great Bend, Kansas License No. 459

Operation Completed: Hour 2 p.m. Day 14 Month 7 Year 1962

The Above well was plugged as follows:

5 1/2" pipe set at 4521'. Perforated from 4489' to 4491'. Sanded to
4470' and 5 sacks cement. 182' of 8 5/8" surface pipe circulated with
cement.. Hole filled with heavy mud to 170' and 10' rock bridge and
20 sacks cement. Hole filled to 40' and second rock bridge and 10
sacks cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/18/62
INV. NO. 5395-W

Signed: Herman Justus
Well Plugging Supervisor