

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Amarillo Natural Gas CompanyComplete Address: Box 1257, Liberal, KansasLease Name Hageman Well No. # 3Location NE NE NE Sec. 15 Twp. 29 Rge. 9 (E) (W) WCounty Kingman Total Depth 4513'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Sargent Casing Pulling ServiceAddress: 121 West 9th, Liberal, Kansas License No. 511Operation Completed: Hour 3:30PM Day 11th Month April Year 1967

The Above well was plugged as follows:

313' of 8 5/8" surface pipe, cemented with 225 sacks. 4513' of 5 1/2" long
string, cemented with 150 sacks. Top perferation 4483'. 15 sacks of cement
was pumped on bottom, with the top of the cement at 3800'. 3018' of 5 1/2"
long string was recovered from the hole. Fluid level in the hole was at
260', bridge plug and rock bridge from 260' to 250', and cemented with
25 sacks. Hole was filled with mud to 40', bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/13/67
INV. NO. 5049-W

Signed: Audie Elving
Well Plugging Supervisor