

*4*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued April 4, 1967.

Operator's Full Name Drillers-Producers Pipe & Supply

*4-24-1967*

Complete Address: P. O. Box 368, Great Bend, Kansas

Lease Name Mueller Well No. # C-1

Location SE SW NW Sec. 14 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4657'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 3:30PM Day 23rd Month April Year 1967

The Above well was plugged as follows:

347' of 8 5/8" surface pipe, cemented with 225 sacks. 4656' of 5 1/2" long  
string, cemented with 150 sacks. Plug back T.D. 4646'. Top perferation  
4473'. Bottom of the hole was sanded to 4450', and cemented with 5 sacks,  
through the dump bailer. 3430' of 5 1/2" long string was recovered from  
the hole. Fluid level in the hole was at 310', bridge plug and rock  
bridge from 310' to 300', and cemented with 25 sacks. Hole was filled  
with mud to 40', rock bridge from 40' to 30', and cemented with 10  
sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 4/24/67  
INV. NO. 5102-w