

40
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1963

CONSERVATION DIVISION
Wichita, Kansas

2-11-1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Herman Geo. Kaiser Oil Producer

Complete Address: 909 Palace Bldg., Tulsa 3, Oklahoma

Lease Name Hageman Well No. # 1

Location 100' W NW SE NW Sec. 15 Twp. 29 Rge. 9 (E) (W)W

County Kingman Total Depth 4518

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Central Pipe Pulling Co.

Address: 1416 Coolidge, Great Bend, Kansas License No. 459

Operation Completed: Hour 4:30PM Day 7th Month Feb. Year 1963

The Above well was plugged as follows:

4516' of 5 1/2" long string cemented with 200 sacks. Plugged back to 4486'.
Perferated from 4480' to 4482'. Sanded to 4460'. 246' of 8 5/8" surface
pipe circulated with cement. Fluid in the hole was at a 40' level. An over
night plug with a 10' rock bridge was set at 200', cemented through the
bailer with 3 sacks cement. Next morning this plug was cemented with 17
sacks cement through the bailer. Hole was filled with mud to 40', 10'
rock bridge, was cemented with 10 sacks to base of the cellar.
3200' of 5 1/2" pipe recivered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/11/63
INV. NO. 6561-W