

DISTRICT CONSERVATION AGENT'S REPORT

*BR*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 58-1

LOCATION NE-SE-NE

SEC. 15 TWP. 29 RGE. 9W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Hegeman

Operator Edna Service Co Address Box 144 Great Bend Kansas

Field \_\_\_\_\_ County Kingman

Total Depth 4498 Feet.

Plugging Contractor C. E. Shull

Plugging Contractor's License No. 8

Address Great Bend Kansas

(Describe Briefly the manner in which the well was plugged)

8 1/2" S.P. 341' C.W.C. 5 1/2" 4490' emit 150 # PB 4471' emit  
Ref 4465'-68' hole filled with sand to 4450' Dumped  
5 # emit Pulled 27 # to 55" gas and salt water flow out at  
Chost 2500' Killed with 200 # Mud. 50 # cement  
Displaced through 5 1/2" with 25 # Mud. Rock fudge set  
300' Dumped 20 # cement. Mud to 35' Rock fudge.  
10 # cement cap. 225 # Mud. 50 # cement pumped by  
Halfpeter Cementing Co

J. L. Pires  
District Conservation Agent

Date 11-18-57

*all salt water caught  
in Eastern pit and pumped  
into Disposal Well.*

PLUGGING  
FILE SEC 15 T 29 R 9W  
BOOK PAGE 58 LINE 1

RECEIVED  
STATE CORPORATION COMMISSION

NOV 21 1957

CONSERVATION DIVISION  
Wichita, Kansas

11-21-1957