


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 33 Twp. 29S Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Quintin Little
Lease Name Millar Well No. 1
Office Address P. O. Box 1509, Ardmore, Okla. 73401
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Feb. 22 19 70
Application for plugging filed (letter 2/24/70) Feb. 22 19 70
Application for plugging approved Feb. 22 19 70
Plugging commenced Feb. 22 19 70
Plugging completed Feb. 22 19 70
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Riberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4710 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	260'	8-5/8"	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 220 feet. Set plug at 220 feet w/1/2 sack hulls and 25 sacks cement. Left upper hole open to be used by landowner for cased water well. Plugged rat hole with 2 sacks cement. Job complete at 9:00 AM, Feb. 22, 1970.

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1970
CONSERVATION DIVISION
Wichita, Kansas
2-25-70

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
830 Sutton Place, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 24 day of February, 19 70
Barbara J. Layton
Barbara J. Layton Notary Public.



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

MILLAR #1
 SE, SE NW Section 33-29S-16W
 Kiowa County, Kansas

Commenced: February 9, 1970
 Completed: February 22, 1970

OPERATOR - Quintin Little

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 25 1970
 CONSERVATION DIVISION
 Wichita, Kansas

DEPTH		FORMATION	REMARKS
From	To		
0	50	Surface clay and shale	
50	135	Sand and red bed	
135	260	Red bed	Ran 8 joints 8-5/8" casing, set @ 260' w/250 sacks cement.
260	1130	Red bed	
1130	1560	Red bed, shale and shells	
1560	2075	Shale and shells	
2075	2148	Lime and shale	
2148	2265	Lime	
2265	4004	Lime and shale	
4004	4425	Lime	
4425	4585	Lime and shale	
4585	4625	Lime	
4625	4651	Lime and chert	
4651	4710	Lime	
4710	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the SE, SE NW Section 33-29S-16W, Kiowa County, Kansas, to the best of my knowledge and belief.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 24 day of February, 1970, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton

 Barbara J. Layton, Notary Public

