

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-221840000

LEASE NAME Mallory A

WELL NUMBER 1-2

1250 Ft. from S Section Line

14030 Ft. from E Section Line

SEC. 1 TWP. 33 RGE. 35 (X) or (W)

COUNTY Stevens

Date Well Completed _____

Plugging Commenced 7-24-98

Plugging Completed 7-28-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mobil E&P USA

ADDRESS 2319 N Kansas Liberal KS 67905

PHONE# (316) 626 1149 OPERATORS LICENSE NO. 5208

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-24-98 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD 8-17-98

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 5/8</u>	<u>601</u>	<u>—</u>
				<u>5 1/2</u>	<u>3077</u>	<u>900</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Mixed 2 sx hulls & 25 sx cmt. to plug perfs from 2697 to 2497, displaced w/mud to 1730 and mixed 25 sx cmt from 1730 to 1530 & displaced w/mud. Shot casing (5 1/2) loose @ 900. Pulled to 650. Circ. hole w/mud & mixed 50 sx plug from 650 to 500. Pulled to 40 & mixed 10 sx plug from 40 to 0. Cut off & capped 8 5/8 4 ft. below G.L.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF Kansas COUNTY OF Seward, ss.


Sharon A. Cook (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Sharon A. Cook

(Address) Box 2173, Liberal KS 67905-2173

SUBSCRIBED AND SWORN TO before me this 14th day of August, 19 98

Gyuh K. Hunt
Notary Public



Expires: 2-20-01