

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-2102 2-0000

LEASE NAME Grey & Grey

WELL NUMBER 4

SPOT LOCATION 330' F S line & 990' F¹E line
SEC. 18 TWP. 29 RGE. 18 (E) or (W)

COUNTY Kiowa

Date Well Completed 8-6-84

Plugging Commenced 10-3-84

Plugging Completed 10-3-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Huey Grey

ADDRESS Rt. 1 Box 47, Greensburg, Kansas 67054

PHONE # (316)-723-3123 OPERATORS LICENSE NO. 8565

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? no if not, is well log attached? Yes

Producing formation None Depth to top none bottom none T.D. 4850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/K.C.	-----	4379	4381	4 1/2	4,837'	2420'
Dennis	-----	4542	4550	same	same	same
Marmaton	-----	4636	4656	"	"	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Welex set a plug at 4660. Pratt well moved off the hole. It was decided that the hole was dry and plugging to be commenced. Halliburton then proceeded to plug the well by the plugging orders gave to them by the KCC. 250 pounds of hulls were put in the hole, after the hulls were pumped in the hole, the gel was started, 15 sacks of gel was then pumped into the hole. The gel was finished and 50 sacks of cement was then put into the hole, after the cement followed 10 sacks of gel, then 125 sacks of cement
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address P.O. Box 963, Pratt, Kansas 67124

RECEIVED
STATE OF KANSAS CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Kiowa, ss.

10-15-84
OCT 15 1984

Huey Grey (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

JONSON ATTORNEY DIVISION
Wichita, Kansas

(Signature) Huey Grey
(Address) Rt. 1 Box 47, Greensburg, KS 67054

SUBSCRIBED AND SWORN TO before me this 11 day of October, 1984

My Commission expires: April 12, 1988

Crystal A. Retzlaff
Notary Public
Crystal A. Retzlaff
NOTARY PUBLIC
State of Kansas
MY COM. EXPIRES 4-12-88

was pumped into the hole. Haliburton finished the cement closed the valve on swage and washed out pumping lines. Then $\frac{1}{4}$ BBL of water was pumped down the casing. The job was complete.