

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-20953-0000

LEASE NAME Grey

WELL NUMBER 2

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 18 TWP. 29S RGE. 18 ~~XXXXX~~ (W)

COUNTY Kiowa

Date Well Completed \_\_\_\_\_

Plugging Commenced 1-30-98

Plugging Completed 2-6-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

FEB 17 1998

2-17-98

LEASE OPERATOR Magnum Oil & Gas

ADDRESS RR #1, Box 49, Greensburg, KS 67054

PHONE# (316) 723-2463 OPERATORS LICENSE NO. 3344

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-30-98 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Miss & Surpc Depth to Top 4395 Bottom 4769 T.D. 5060

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size  | Put In | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 415    | None       |
|           |         |      |    | 4 1/2 | 5060   | 2900       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Lay down rods and tubing, set CIBP at 4327, dump 2sx cement with dump bailor, stretch and cut pipe at 2900, lay down casing. Allied pump 300 hulls, 10 jel, 50sx cement, 10 jel, 100 hulls 8 5/8 wipter plug and 150sx cement, 60/40 6% jel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Magnum Oil & Gas Inc.

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.



(Signature) [Signature]

(Address) Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 14 day of February, 19 98

Glenda Morrison  
Notary Public

My Commission Expires: 10/14/98