


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Kingman County. Sec. 10 Twp. 29S Rge. 9 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines NW SW NW
Lease Owner Murphy Oil Company of Oklahoma, Inc.
Lease Name L. M. Laggart Well No. 1
Office Address 400 Midstates Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed December 28, 1957
Application for plugging filed December 28, 1957
Application for plugging approved December 28, 1957
Plugging commenced December 28, 1957
Plugging completed December 28, 1957
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. M. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4545 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red bed & shale		0	280'	8-5/8"	280'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Set wooden plug at 250', 1/2 sack hulls on top and filled to 35' with 20 sacks of cement. Set wooden plug at 35', 1/2 sack of hulls on top and filled to bottom of cellar with 10 sacks of cement. Welded iron cap on top of pipe.

1-4-58

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1958

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barbour Drilling Company
Address 1612 First National Building, Tulsa 3, Oklahoma CONSERVATION DIVISION
Wichita, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
E. W. Pribyl (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BARBOUR DRILLING COMPANY

(Signature) E. W. Pribyl
1612 First National Building, Tulsa 3, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 1958

Merry Jane Burt
Notary Public.

My commission expires July 27, 1961

PLUGGING
TR SEC 10 T 29 R 9W
BOOK PAGE 72 LINE 36

LAGGART, L.M. #1

NW SW NW Section 10-29S-9W
Kingman County, Kansas
Murphy Oil Company of Oklahoma Inc.

8-5/8" O. D. casing cemented at 280'

Drilling commenced December 9, 1957
Drilling completed December 28, 1957

FROM	TO	FORMATION	REMARKS
0'	90'	Sand & clay	
90	255	Red bed & shells	
255	1100	Red bed & shale	8-5/8" O. D. casing cemented with 250 sacks cement at 280'
1100	1490	Shale & shells	
1490	1630	Shale & lime	
1630	1940	Lime & shale	
1940	2100	Lime	
2100	2280	Lime & shale	
2280	2695	Shale	
2695	3170	Shale & lime	
3170	3315	Lime	
3315	3388	Shale, lime & sand	
3388	3390	Shale	
3390	3475	Lime, shale & sand	
3475	3540	Shale & lime	
3540	3885	Lime	
3885	3920	Lime (Hard)	
3920	3980	Lime	
3980	4030	Lime & shale	
4030	4085	Lime	
4085	4161	Shale & lime	
4161	4173	Mississippi chat	
4173	4235	Chat	
4235	4265	Lime & chat	
4265	4290	Lime & shale	
4290	4458	Shale	
4458	4468	Viola lime	
4468	4515	Lime	
4515	4531	Shale & sand	
4531	4545	Shale	Well plugged-dry hole
T.D.	4545'		

This is a true copy of the driller's log as shown on the drilling tickets.

PLUGGING
IN SEC 10 T 29 R 9W
BOOK PAGE 72 LINE 36

BARBOUR DRILLING COMPANY

By: E. W. Pibyl RECEIVED
S. J. BROWN COMMISSION

Subscribed and sworn to before me on this 3 day of January, 1958.

JAN 4 1958

My commission expires July 27, 1961

Merry Jane Burt CONSERVATION DIVISION
Notary Public Wichita, Kansas