


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

# WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County. Sec. 15 Twp. 29S Rge. 9W ~~XX~~ ~~XX~~  
Location as "NE/CNW/SW" or footage from lines SW NE NW  
Lease Owner Anschutz Oil Co., Inc.  
Lease Name Hageman Well No. 3  
Office Address 350 Denver Hilton Office Bldg., Denver, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed December 7 19 56  
Application for plugging filed June 28 19 62  
Application for plugging approved July 5 19 62  
Plugging commenced July 11 19 62  
Plugging completed July 14 19 62  
Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production April 30 19 62  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justice  
Producing formation Viola Depth to top 4489 Bottom 4525 Total Depth of Well 4525 Feet  
Show depth and thickness of all water, oil and gas formations.

### OIL, GAS OR WATER RECORDS

### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Viola</u>	<u>oil</u>	<u>4489</u>	<u>4525</u>	<u>5 1/2"</u>	<u>4521.70</u>	<u>3424</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \* feet to feet for each plug set.  
\* Plugged back to 4470 feet and dumped 5 sacks cement; bailed hole to 180 feet; set 10 feet rock bridge; dumped 20 sacks cement; mudded hole to 40 feet; dumped 10 sacks cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 8 1962  
CONSERVATION DIVISION  
Wichita, Kansas

8-8-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Central Pipe Pulling Co.  
Address 1416 Coolidge, Great Bend, Kansas

STATE OF Colorado, COUNTY OF Denver, ss.  
John D. Haley (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John D. Haley  
350 Denver Hilton Office Bldg., Denver, Colo.  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 62

My commission expires August 28, 1965

Herman E. Klump  
Notary Public.



RECEIVED  
STATE CORPORATION COMMISSION

JUL 5 1962

CONSERVATION DIVISION  
Wichita Kansas

Well Log

Hageman #3  
SE NE NW 15-29S-9W  
Kingman County, Kansas


0	-	50	Sand and clay		
50	-	188	Shale and shells		
188	-	530	Red rock and shale		
530	-	750	Shale and red bed	<u>Top of Formation</u>	
750	-	1195	Shale and shells		
1195	-	1235	Anhydrite	Anhydrite	1195
1235	-	1395	Shale and shells	Heebner	3352
1395	-	1685	Lime	Toronto	3371
1685	-	1875	Lime and shale	Douglas	3379
1875	-	2005	Lime	Douglas sand	3430
2005	-	3380	Lime and shale	Lansing	3561
3380	-	3510	Douglas shale and sand	Mississippi	4188
3510	-	3561	Douglas shale	Kinderhook	4299
3561	-	4112	Lansing lime	Viola	4489
4175	-	4197	Lime and shale		
4197	-	4280	Mississippi chat & lime		
4280	-	4492	Shale and lime		
4492	-	4525	Viola		
4525	-		TD		

State of Kansas SS  
County of Barton

T. D. Sweetman, president of Dutch Drilling Co., Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

  
T. D. Sweetman

Subscribed and sworn before me this 5 th day of December, 1956.

  
Dick B. Evans  
Notary Public Barton County

My Commission expires May 9, 1959