


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Kingman County. Sec. 14 Twp. 29 Rge. 9 (W)
Location as "NE/CNWSW" or footage from lines NE/NE/NW
Lease Owner Aurora Gasoline Company
Lease Name Mueller Well No. #1
Office Address 1107 Un. Natl. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 8-9 19 58
Plugging completed _____ 8-24 19 58
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4525' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				5 1/2"		3,567'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 4525'.
Plugging started 8-9-58. Finished 8-24-58.
Plugged off bottom and put in 70 ft. sand. Dumped 5 sacks cement.
Shot 5 1/2" casing at 3,567'. Circulated and spotted 100 bbls oil.
Mixed and circulated 96 sacks mud. Squeezed well, using 4 sacks mud and 100 sacks cement. Well completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 1958

My commission expires November 8, 1960.
Betty S. Edman Notary Public.

PLUGGING
FILE SEC. 14 T. 29 R. 9W
BOOK PAGE 122 LINE 6

STATE CORPORATION
SEP 3 1958
CONSERVATION DIVISION

MUELLER #1

Casing Record: Company: Aylward Drilling Company Location: NE NE NW
8-5/8" 172' Contractor: Aylward Drilling Co. Sec. 14-29-9W
5-1/2" 4525' Kingman County, Kansas

Commenced: August 11, 1954 Elevation: 1700 D.F.
Completed: August 27, 1954

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand & Clay	0	80	<u>Cable Tool Data</u>
Redbed	80	530	
Shale & Shell	530	840	
Shale	840	1250	Cleaned out, perforated 48 holes
Salt	1250	1370	4486' to 4496'. Filled up to 2200'
Lime	1370	1630	of oil in 30 minutes. Flow 20
Lime & Shale	1630	2385	to 30 B.O.B.H.
Shale	2385	2435	
Lime & Shale	2435	3590	
Lime	3590	4034	<u>GEOLOGICAL TOPS</u>
Lime & Shale	4034	4077	Heebner 3338
Lime	4077	4331	Douglas 3376
Lime & Shale	4331	4406	Lansing 3562
Shale	4406	4465	Mississippian 4204
Viola	4465	4495	Viola 4485
Lime	4495	4525 T.D.	

I certify that this is a true and correct copy of the above log to be best of my knowledge;

Paul W. Hesse

Subscribed and sworn to before me this 26th day of November, 1954.

RECEIVED
CONSERVATION COMMISSION

AUG 9 1958

CONSERVATION DIVISION
Wichita, Kansas
PLUGGING
FILE SEC. 14. T. 29. R. 9W.
BOOK PAGE 122 LINE 6