

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FORM CP-1  
Rev. 6/4/84

MAR 02 1989  
3-2-1989  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-097-20,986-0000 (of this well) 6/89  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO PRODUCTION CORPORATION OPERATORS LICENSE NO. 5171

ADDRESS 1660 Lincoln Street, Suite 1800, Denver, CO 80264 PHONE # (303) 861-4246

LEASE (~~FARM~~) UNRUH-GREY WELL NO. 2 WELL LOCATION 350' FSL 2070' COUNTY Kiowa

SEC. 18 TWP. 29S RGE. 18 (~~E~~) of (W) TOTAL DEPTH 4800 PLUG BACK TD 4760'

Check One:

OIL WELL \_\_\_\_\_ GAS WELL X D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 433' CEMENTED WITH 200 SACKS

CASING SIZE 4 1/2" SET AT 4795' CEMENTED WITH 200 SACKS

PERFORATED AT Swope 4644-52', LKC 4752-55', Plug @4530', LKC "B" 4412-18'  
(squeezed w/100 sxs) Cmt. Ret. @4390', L-KC "G" zone 4504-07'

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Dump 100 gals sand dn Csg., dump bail 4 sxs

Cmt. Recover ± 3000' 4 1/2" csg. Plug surface w/4 sxs hulls, 25 sxs 60-40 poz-mix w/6% gel 1 sx

hulls 100 sxs 60-40 poz-mix w/6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN TO BE COORDINATED WITH TXO & KCC OFFICES.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

LEAMON ROBERSON

PHONE # (316) 886-5606

ADDRESS P.O. BOX 125B, Medicine Lodge, KS 67104

PLUGGING CONTRACTOR CLARK CORPORATION

LICENSE NO. 5105 6/89

ADDRESS 107 W. Fowler, Box 187, Medicine Lodge, KS

PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: \_\_\_\_\_

Leamon Roberson  
(Operator or Agent)

DATE: \_\_\_\_\_

2-28-89

(1)

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE  
JUN 3 1989  
EXPIRES

March 3, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

TXO Production Corporation  
1660 Lincoln Steet  
Wichita, KS 80264

Unruh-Grey #2  
350' FSL 3219' FEL  
Sec. 18-29S-18W  
Kiowa County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*  
Shari Feist Albrecht  
Director

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760