

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

RECEIVED

FORM CP-1  
Rev. 6/4/84

OCT 14 1988  
10-14-1988

WELL PLUGGING APPLICATION FORM  
(File One Copy)  
CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER 15-097-21083-0000 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO PRODUCTION CORP. OPERATORS LICENSE NO. 5171

ADDRESS 1660 Lincoln St. Suite 1800 PHONE # (303) 861-4246

LEASE (~~FARM~~) Unruh-Grey WELL NO. 4 WELL LOCATION 2310<sup>th</sup> TWP COUNTY Kiowa

SEC. 18 TWP. 29S RGE. 18  (W) TOTAL DEPTH 4900' PLUG BACK TD 4886' Float  
4536' CIBP

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. -

SURFACE CASING SIZE 8 5/8" SET AT 412' CEMENTED WITH 350 SACKS

CASING SIZE 4 1/2" SET AT 4899' CEMENTED WITH 300 SACKS

PERFORATED AT 4504'-15' LKC "G" & 4382'-7' LKC "A"

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plug bottom w/10 sxs cmt., 1 sx hulls, rubber plug. Cut and pull 4-1/2" casing, ±3500'. Plug top w/5 sxs hulls, 10 sxs gel and 100 sxs 60/40 poz-mix.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED? yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be coordinated with field office.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leamon Roberson PHONE # (316) 886-5606

ADDRESS P.O. Box 125B Medicine Lodge, Kansas 67104

PLUGGING CONTRACTOR Clarke Corporation LICENSE NO. 5105

ADDRESS 107 W. Fowler, Box 187 Medicine Lodge, KS PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Cory West  
(Operator or Agent)

DATE: October 12, 1988

①

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

October 17, 1988

JAN 17 '89

WELL PLUGGING NOTICE

EXPIRES

Unruh-Grey #4  
650' FSL 2970' FEL  
Sec. 18-29S-18W  
Kiowa County

TXD Production Corporation  
1660 Lincoln St., Ste. 1800  
Denver, CO 80264


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #1 304 W. McArtor, Dodge City, KS 67801 (316) 225-6760