


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Kiowa County, Sec. 28 Twp. 29 Rge. (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines C S/2 SE SW
Lease Owner Rupp-Ferguson Oil Co.
Lease Name Barstow Well No. 1
Office Address 523 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-26-55 19
Application for plugging filed 9-26-55 19
Application for plugging approved 9-26-55 19
Plugging commenced 9-26-55 19
Plugging completed 9-26-55 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4925 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 13 3/8 | 250 | 0 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 248, 1/2 sack hulls. Plug - 30 sacks cement thru d.p. Mud to 20', 1/2 sack hulls. Plug tied. Filled to cellar base with cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 523 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I. W. Knox (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. W. Knox
523 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 1955

My commission expires June 4, 1959.

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1955

CONSERVATION DIVISION
Wichita, Kansas

9-29-1955

PLUGGING
FILE SEC 28 T 29 R 17 W
BOOK PAGE 2 LINE 43

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Barstow
C.S/2 SE SW, Sec. 28-29-17W,
Kiowa County, Kansas

D. & A

Elev. 2154 KB.

Contractor: Rupp-Ferguson Oil Co.
Commenced: 9-8-55
Completed: 9-26-55

Set 250' of 13 3/8" surface casing w/225 sacks cement.

Figures Indicate Bottom of Formation

- 74 clay, shale & shells
- 88 sand
- 125 sand rock
- 295 blue shale
- 330 sandstone & shale
- 455 red bed
- 470 lime
- 1030 red bed
- 1085 red bed & shale
- 1480 lime & shale
- 1590 salt, shale streaks
- 2245 shale & shells
- 3801 lime & shale
- 3949 lime
- 4032 lime, shale streaks
- 4225 lime & shale
- 4280 lime, shale & sand
- 4797 lime
- 4843 lime & shale
- 4925 Miss. T.D.

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify the above and foregoing to be a true and correct copy of the log of the No. 1 Barstow well.

L. W. Knox
L. W. Knox

Subscribed and sworn to before me this 28th day of September, 1955.

Helen Horner
Notary Public
NOT COMMISSION

My Commission Expires June 4, 1959. CL 29-1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 28-29-17W
BOOK PAGE 2 LINE 43