

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kiowa County. Sec. 30 Twp. 29 Rge. 17 ~~18~~ (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner Aurora Gasoline Co. & Aylward Drilling Company

Lease Name Jenkins Well No. 1

Office Address 813 1st Natl. Bank Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 25 1956

Application for plugging filed January 25 1956

Application for plugging approved January 25 1956

Plugging commenced January 26 1956

Plugging completed January 26 1956

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4940 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	125'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 4940' to 120'; set Halliburton plug with 1/3 sack hulls and rock bridge with 20 sacks cement from 120' to 60'; heavy mud from 60' to 35'; Halliburton plug with 1/3 sack hulls and rock bridge with 15 sacks cement from 35' to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company

Address 813 First National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Paul W. Hesse (employee of owner) ~~known operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse

813 1st Natl. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of January, 1956

Duane Jessup Notary Public.

My commission expires December 11, 1957

PLUGGING
FILE SEC 207 29 R 17W
BOOK PAGE 34 LINE 20

RECEIVED
DATE CORRECTED
FEB 1 1956
CONSERVATION DIVISION
Wichita, Kansas
2-1-1956

JENKINS #1

Casing Record: 8 5/8" - 125'

COMPANY: Aylward Drilling Company

CONTRACTOR: Aylward Drilling Company

COMMENCED: January 6, 1956

COMPLETED: January 23, 1956

Location: NW NW SW Sec. 30-29-17W
 Kiowa County, Kansas

Elevation: 2068'

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Silt	0-	12	GEOLOGICAL TOPS: Heebner 4033 Toronto 4047 Douglas 4082 Brown Lime 4205 Lansing/K.C. 4223 Base Kansas City 4568 Cherokee 4762 Conglomerate 4828 Mississippian 4838 D.S.T. 4828-64 Miss., open 1 hr., Rec. 940' muddy salt water & gas cut scum oil, BHP 1590#, FP 1501 in 20", FFP 450#.
Blue Shale	12	112	
Gray Shale	112	310	
Sand	310	340	
Red Bed	340	980	
Shale and Shells	980	1950	
Sandy Shale	1950	2145	
Lime and Shale	2145	2190	
Shale with lime streaks	2190	2275	
Lime	2275	2365	
Shale & Lime	2365	2545	
Shale and Shells	2545	2655	
Shale and lime	2655	3060	
Shale and broken lime	3060	3425	
Shale and Lime	3425	3505	
Shale and broken lime	3505	3630	
Shale and Lime	3630	3755	
Shale and broken lime	3755	3940	
Shale and Lime	3940	3955	
Lime	3955	4070	
Lime and Shale	4070	4250	
Lime	4250	4580	
Hard Lime	4580	4620	
Lime and Shale	4620	4655	
Lime	4655	4709	
Lime and Shale	4709	4780	
Lime	4780	4810	
Lime and Shale	4810	4830	
Conglomerate	4830	4838	
Chert	4838	4864	
Chert and Shale	4864	4904	
Chert	4904	4940	

R.T.D. D. & A.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse
 Paul W. Hesse

Subscribed and sworn to before me this 31st day of January, 1956.

Duane Jessup
 Duane Jessup - Notary Public

My commission expires December 11, 1957.

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 1 1956
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 20 T 29 R 17W
 BOOK PAGE 34 LINE 20