

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Kiowa SEC. 8 TWP. 29 RGE. 19 ~~EW~~  
Location as in quarters or footage from lines:  
C/NW/NE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Petroleum, Inc.  
Lease Name Witt "K" Well No. #1  
Office Address Box 1447 - Great Bend, Ks. 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced June 02, 1982  
Plugging completed June 22, 1982  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 5110'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	562'	NONE
				4 1/2"	5108'	2437.95'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Dumped sand to 4950' and five (5) sacks cement.  
Shot pipe @ 4500', 4300', 4000', 3600', 3200', 3000' and 2430'.  
Pulled seventy-five (75) joints of 4 1/2" casing.  
Squeezed well with ten (10) sacks gel, six (6) sacks hulls,  
fifteen (15) sacks gel, one hundred fifty (150) sacks 50/50  
pozmix cement with 2% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.


James W. Rockhold (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature)

James W. Rockhold  
JAMES W. ROCKHOLD Box 698 - Great Bend,  
(Address) Ks. 67530

SUBSCRIBED AND SWORN TO before me this 6th day of July, 19 82

My Commission expires:



RECEIVED Public.  
STATE CORPORATION COMMISSION

JUL 9 1982

CONSERVATION DIVISION  
Wichita, Kansas

# WELL LOG

COMPANY **Petroleum, Inc.** SEC. 8 T. 29S R. 19W  
 FARM **Witt 'K'** NO. 1 LOC. C NW NE  
 TOTAL DEPTH **5110'** COUNTY **Kiowa, Kansas**  
 COMM. **10-2-72** COMP. **10-15-72**  
 CONTRACTOR **Garvey Drilling Company**


CASING  
 8 5/8" @ 562' w/425bx  
 4 1/2" @ 5108' w/150bx

ELEVATION 2356' KB

PRODUCTION MISSISSIPPI

FIGURES INDICATE BOTTOM OF FORMATIONS

- 180' Shale & Sand
- 280' Sand
- 610' Shale
- 925' Sand
- 1193' Shale
- 1218' Anhydrite
- 1290' Shale
- 2445' Shale & Lime Streaks
- 2540' Lime
- 3350' Lime & Shale
- 3475' Lime
- 4120' Lime & Shale
- 4340' Lime
- 5032' Lime & Dolomite
- 5110' Mississippian
- 5110' RTD

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 27 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas }  
 County of Barton } SS

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Witt 'K' #1 well.

Subscribed and sworn to before me this 17th day of October, 1972

My Commission Expires: July 8, 1974

*Charlene Marker*  
 \_\_\_\_\_  
*James C. [Signature]*  
 \_\_\_\_\_  
 NOTARY PUBLIC

