


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Kiowa County, Sec. 25 Twp 29S Rge. (E) 19 (W)  
Location as "NE/CNW%SW%" or footage from lines C NE NE SW  
Lease Owner Gulf Oil Corporation  
Lease Name B. R. Bockhaus Well No. 1  
Office Address Box 661, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-6-19 55  
Application for plugging filed 10-7-19 55  
Application for plugging approved 10-7-19 55  
Plugging commenced 10-8-19 55  
Plugging completed 10-8-19 55  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5070 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	666'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled w/mud to 594', 1/2 sack hulls & HOWCO cementing plug pushed to 594'. 35 sacks Pozmix cement spotted through drill pipe @ 594', mud to 35', 1/2 sack hulls, HOWCO plug @ 35', 15 sacks cement filled into cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Falcon-Seaboard Drilling Company  
Address East Mezzanine, Stanolind Building, Tulsa 3, Oklahoma

STATE OF Kansas, COUNTY OF Rice, ss.  
W. H. Duley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley  
Box 544, Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of October, 1955

My commission expires April 14, 1956

W. M. Council Notary Public.

PLUGGING  
FILE SEC 25 29 R 19 W  
BOOK PAGE 7 LINE 16

RECEIVED  
STATE CORPORATION COMMISSION

10-13-1955  
Wichita, Kansas

COPY

WELL NO. 1 LEASE B. R. Bockhaus COMPANY Gulf Oil Corporation A.F.E. 6252  
 DATE DRILLING BEGAN 9-12-55 WELL COMPLETED 10-8-55 FIRST PRODUCTION Dry  
 SAND RECORD Dry Hole - Plugged and Abandoned TOTAL DEPTH 5070'

INITIAL PRODUCTION:

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LES. CAL. CHLO.	PULLED	LEFT IN.
8-5/8"	*	*	*	*	676'	425	2%		676'
* 2 jts 32#, 10V, C-1, LW 15 jts 23#, NT, A, Armco slip jt. 1 jt 32#, 8R, C-1, LW									

S- 25 T- 29S R-19W

				Center
				NE
				NE
				SW
		X		Kiowa
				County,
				Kansas

Distance H- 10' from RKB to top 8-5/8" casing

ELEVATION- DFE 2311'  
KBE 2314'

- 0 to 71' Surface Soil & Clay
- 539 Clay & Sand
- 685 Bentonite, Lime & Shale
- 1685 Red Bed
- 2539 Lime & Shale
- 3073 Lime
- 3176 Lime & Shale Stks.
- 3653 Shale & Lime
- 3819 Lime
- 4658 Lime & Shale
- 4808 Lime
- 4869 Lime & Shale
- 4920 Lime
- 4923 Core No. 1
- 4972 Core No. 2
- 4990 Core No. 3
- 5012 Core No. 4
- 5013 Shale
- 5019 Core No. 5
- 5033 Lime
- 5070 Lime & Shale
- 5070 TOTAL DEPTH

COPY

Copy:  
12-7-55  
:JRM

**PLUGGING**  
 FILED SEC 25 T 29 R 19W  
 BOX PAGE 2 LINE 16

RECEIVED  
 NOV 20 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas