

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County. Sec. 33 Twp. 29 Rge. 19 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner Aylward Drilling Company et al

Lease Name Wykle Well No. 1

Office Address 813 1st National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 20 19 56

Application for plugging filed February 20 19 56

Application for plugging approved February 20 19 56

Plugging commenced February 20 19 56

Plugging completed February 20 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 5220 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	495'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 490'; cement plug from 490' to 430' with 20 sacks; heavy mud from 430' to 35'; cement plug from 35' to top of surface pipe with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company  
Address 813 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Paul W. Hesse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse  
813 1st National Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of February, 1956

My commission expires December 11, 1957

Duane Jessup  
Notary Public.

STATE CORPORATION COMMISSION

FEB 29 1956

CONSERVATION DIVISION  
Wichita, Kansas

2-29-1956

**PLUGGING**  
 FILE SEC 33 T 29 R 19  
 BOOK PAGE 40 LINE 9

WYKLE # 1

Casing Record:

8 5/8" = 495'

COMPANY: BACHUS OIL CO. AND  
AYLWARD DRILLING COMPANY

CONTRACTOR: Aylward Drilling Company

Location: SW SW SE  
Sec. 33-29-19W  
Kiowa County  
Kansas

COMMENCED: January 27, 1956  
COMPLETED: February 20, 1956

Elevation: 2320 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Clay and Sand	0	40	Set 8 5/8" casing @ 495' w/300 sacks cement.
Sandy, Gray Clay	40	360	
Red Bed	360	410	D.S.T. 5050-65, open 15 min., init. shutin press. 80#, rec. 30# mud, IFP & FFP 60#
Sand	410	440	
Red Bed & Shells	440	570	
Red Bed & Shale	570	950	
Anhydrite	950	970	
Shale & Shells	970	1075	
Shale, Shells & Salt	1075	1235	
Red Bed & Shells	1235	1535	
Shale & Shells	1535	2285	
Lime & Shale	2285	2545	
Lime	2545	2800	Geological Tops: Heebner 4282 Douglas 4360 Brown Lime 4467 Lansing/Kansas City 4487 Base/Kansas City 4864 Mississippian 5120
Lime & Shale	2800	2950	
Lime	2950	3050	
Lime with shale strks.	3050	3140	
Lime & shale	3140	3450	
Shale & shells	3450	3525	
Shale & Lime	3525	4050	
Lime	4050	4295	
Lime & shale	4295	4333	
Sand, Lime & shale	4333	4480	
Lime & shale	4480	4508	
Lime	4508	4700	
Lime & shale	4700	4745	
Lime	4745	4810	
Lime & shale	4810	4849	
Lime & shale	4849	4901	
Lime & shale	4901	5065	
Lime	5065	5124	
Lime & chert	5124	5181	
Lime	5181	5220 TD	D. & A.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

*Paul W. Hesse*  
Paul W. Hesse

Subscribed and sworn to before me this 27th day of February, 1956

*Duane Jessup*  
Duane Jessup Notary Public

My commission expires December 31, 1957

REI  
STATE COM  
FEB 27  
CONSERVATION  
Wichita, Kan.

**PLUGGING**  
SEC 33 T 29 R 19W  
BOX 40 LINE 9