


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Kiowa County, Sec. 31 Twp. 29S Rge. (E) 19 (W)
Location as "NE/CNWKSWK" or footage from lines 668.1' FEL & 2036.5' FSL
Lease Owner Anadarko Production Company
Lease Name Ralstin "A" Well No. 1
Office Address Box 351, Liberal, Kansas 67901
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 22 19 70
Application for plugging filed May 25 19 70
Application for plugging approved Verbal approval received 5-21 19 70
Plugging commenced May 21 19 70
Plugging completed May 22 19 70
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas 67009
Producing formation Depth to top Bottom Total Depth of Well 5373 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	571'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 45 sacks cement from 500' to 410'

Spotted 15 sacks cement from 40' to surface.

Hole filled with mud between plugs.

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bowers Drilling Company
Address Wichita Plaza Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Seward, ss. W. K. Downey (employee of owner) or (owner or operator) of the above-described


well, being duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. K. Downey*

Box 351, Liberal, Kansas 67901 (Address)

Subscribed AND SWORN TO before me this 25th day of May, 19 70

J. W. Williams
Notary Public.



My commission expires

My Commission Expires April 28, 1971

DRILLER'S LOG

WELL NAME Ralstin "A" No. 1 COMPANY OPERATING Anadarko Production Company
 ADDRESS OF COMPANY Box 351, Liberal, Kansas 67901
 WELL LOCATION 1/4 NE 1/4 SE 1/4
2036.5 Ft. North of South Line,
4741 Ft. East of West Line, Sec. 31, Twp. 29S, Rge. 19W, Kiowa County, Kansas
 DRILLING STARTED 5-6, 19 70, DRILLING COMPLETED 5-22, 19 70
 WELL COMPLETED 5-22, 19 70, WELL CONNECTED _____, 19 _____
 ELEVATION 2369.0 Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 27 1970
 CONSERVATION DIVISION
 Wichita, Kansas

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
10 3/4"	517'	450	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface sand & clay	0	90	Lime	4465	4545
Shale, sand, redbed	90	518	Lime & shale	4545	4685
Redbed & shale	518	1175	Lime	4685	4745
Redbed	1175	1528	Lime & shale	4745	4835
Shale	1528	1689	Lime	4835	5373
Shale & lime	1689	2455	Total depth	5373	
Lime	2455	2585			
Lime & shale	2585	2940			
Lime	2940	3011			
Lime & shale	3011	3910			
Shale & lime	3910	4160			
Lime & shale	4160	4350			
Shale & lime	4350	4465			

RESULTS OF INITIAL PRODUCTION TEST: _____

