


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 27 Twp. 29 Rge. 16 (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Aylward Drilling Company et al
Lease Name Rezeau Well No. 1
Office Address 813 1st Natl. Bank Bldg. - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 4 1956
Application for plugging filed January 4 1956
Application for plugging approved January 4 1956
Plugging commenced January 4 1956
Plugging completed January 4 1956
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. A. Rives - Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4718' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 130' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 4718' to 131'; set Halliburton plug with 20 sacks of cement to 90'; heavy mud from 90' to 30' with plug on top of 1/4 sack of hulls and 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company
Address 813 First Natl. Bank Building - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Paul W. Hesse (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse
813 1st Natl. Bank Bldg. - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1956

My commission expires December 11, 1957

Duane Jessup
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 27 T 29 R 16W
BOOK PAGE 29 LINE 40

JAN 11 1956
CONSERVATION DIVISION
WICHITA

1-11-1956

REZEAU #1

Casing Record:

Company: Aylward Drilling Company

Location:

8-5/8" - 131'

Contractor: Aylward Drilling Company

NE NE NE Sec. 27-29-16W
Kiowa County, Kansas

Commenced: December 18, 1955

Elevation: 1987 D.F.

Completed: January 4, 1956

| | <u>From</u> | <u>To</u> | <u>Remarks</u> |
|----------------------|-------------|-----------|---|
| Red Bed | 0 | 15 | DST 4704-18, open 30 min., rec. 5' mud, BHP 210# |
| Sand | 15 | 35 | |
| Blue Shale | 35 | 155 | |
| Red Bed | 155 | 310 | GEOLOGICAL TOPS: |
| Shale | 310 | 875 | |
| Anhydrite | 875 | 908 | Anhydrite 875 |
| Shale & Shells | 908 | 1860 | Heebner 3925 |
| Lime & Shale | 1860 | 1930 | Toronto 3946 |
| Lime | 1930 | 2545 | Douglas Sand 3981 |
| Lime & Shale | 2545 | 2665 | Brown Lime 4081 |
| Lime | 2665 | 2725 | Lansing 4097 |
| Lime & Shale | 2725 | 3700 | Base Kan. City 4436 |
| Lime | 3700 | 3835 | Cherokee Shale 4613 |
| Lime & Shale | 3835 | 3950 | Residual Miss. 4642 |
| Lime & Sand | 3950 | 4035 | Kinderhook Shale 4654 |
| Lime | 4035 | 4220 | Viola 4702 |
| Lime Chert | 4220 | 4260 | |
| Lime | 4260 | 4365 | |
| Lime Chert | 4365 | 4420 | |
| Lime & Shale Streaks | 4420 | 4445 | |
| Lime & Shale | 4445 | 4510 | |
| Lime | 4510 | 4565 | |
| Lime & Shale | 4565 | 4654 | |
| Chert | 4645 | 4654 | |
| Shale | 4654 | 4702 | |
| Viola Lime | 4702 | 4718 | R.T.D. D. & A. |

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse
Paul W. Hesse

Subscribed and sworn to before me this 10th day of January, 1956.

Duane Jessup
Duane Jessup - Notary Public

My commission expires December 11, 1957

PLUGGING
FILE SEC 27 T 29 R 16W
BOOK PAGE 29 LINE 40

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1956

COUNCIL OF DISTRICTS