

API NUMBER 1509720492-0001

LEASE NAME CONKLIN

WELL NUMBER #1-9

3960 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 9 TWP. 29S RGE. 17W (E) or (W)

COUNTY KIOWA COUNTY

Date Well Completed 11/5/91

Plugging Commenced 4/3/95

Plugging Completed 4/3/95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR MOLITOR OIL, INC.

ADDRESS P.O. BOX 74 SPIVEY, KANSAS 67142

PHONE# (1) 316-243-6773 OPERATORS LICENSE NO. 3067

Character of Well OIL WELL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/3/95 (date)

by MR. STEVE DURRANT (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? NOT AVAILABLE

Producing Formation MISSISSIPPI Depth to Top 4749' Bottom 4784' T.D. 4808'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
MISSISSIPPI	OIL WELL	SURFACE	4808'	5 1/2"	7 7/8" HOLE	2707' OF 5 1/2" CASING

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

WE PLUGGED THIS WELL WITH 300 LBS. COTTON SEED HULLS; THEN 10 SKS. OF GEL; THEN 50 SKS. 60/40 POZMIX CEMENT 6% GEL; THEN 10 SKS. OF GEL; THEN 100 LBS. COTTON SEED HULLS. SHUT DOWN RUN 8 3/8" WIDER PLUG AND RUN 150 SKS. 60/40 POZMIX CEMENT WITH 6% GEL AND SHUT WELL IN. WENT BACK 4/3/95 AND RUN 9 SKS. CEMENT TO FILL TO TOP SURFACE PIPE.

Name of Plugging Contractor GREENSBURG WELL SERVICE License No. 31201

Address GREENSBURG, KANSAS 67054 303 E. KANSAS P.O. BOX 362

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MOLITOR OIL, INC.

STATE OF KANSAS COUNTY OF KIOWA, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Janet A. Molitor

(Address) R.R. 1 Box 74 Spivey, KS 67142

SONDRA BOYCE
NOTARY PUBLIC
STATE OF KANSAS

My Appt. Exp. 4-21-99 SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 95

Sondra Boyce
Notary Public

My Commission Expires: 4-21-99