


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 12 Twp. 29S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines NW SE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Hubert Well No. 1
Office Address Union National Bldg. Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Drv Hole
Date well completed March 30th 19 57
Application for plugging filed March 29th 19 57
Application for plugging approved March 29th 19 57
Plugging commenced March 30th 19 57
Plugging completed March 30th 19 57
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. River
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5010 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	602'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy Rotary Mud to 350' Set Halliburton Plug at 350'
20 Sacks Cement Thru Drill Pipe. Filled hole to 30' of bottom of cellar
Plug at 30' ~~with~~ 10 Sacks Cement on Plug.

RECEIVED
STATE CORPORATION COMMISSION

APR 6 - 1957
CONSERVATION DIVISION
Wichita, Kansas
4-6-1957

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Patton Drilling Company, Inc.
Address 505 Orpheum Bldg. Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert W. Patton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert W. Patton
505 Orpheum Bldg. Wichita 2, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 57
T. P. Hendrick
Notary Public.

My commission expires Oct 4th 1960

PLUGGING
FILE SEC 12 T. 29 R. 18W
BOOK PAGE 3 LINE 15

Imperial Oil of Kansas Inc.
 Hubert Well # 1
 Total Depth 5010'
 Comm. 2/28/57
 Comp. 3/30/57
 Contractor Patton Drilling Company, Inc.

Location; NW $\frac{1}{4}$ SE $\frac{1}{4}$ of Section 12-T29S
 R18W Kiowa County, Kansas.
 CASING RECORD
 8 5/8" 24# Casing at 602'
 Cemented with 450 Sacks Cement

Soil & Yellow Clay	120
Sand & Clay	150
Sand & Gravel	225
Blue Shale	380
Red Bed Shells	550
Anhydrite Red Bed	620
Shale & Shells	2090
Lime & Shale	3860
Lime	4162
Lime & Shale	4333
Lime K.C.	4439
Lime & Chert	4485
Lime	4601
Lime & Shale	4911
Lime	4915
Cored	4938
Lime Chert	4980
Lime	5010
Total Depth	5010

10' off Kelly Bushing to Ground level.

STATE OF Kansas COUNTY OF Ledwich ss.

I, the undersigned, being duly sworn, on oath state the above statement and log is a true and correct record and log of the well drilled at the location above described.

PATTON DRILLING COMPANY, INC.

By Robert W. Patton

Subscribed and sworn to before me this 3rd day of April 1957

T. P. Hendrick
 T. P. Hendrick Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION
 1960

My Commission expires Oct 4th 1960

PLUGGING
 FILE SEC 12 T 29 R 18W
 BOOK PAGE 3 LINE 15