


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 11 Twp. 29S Rge. 16 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines SW SW NW
Lease Owner Imperial Drilling Co.
Lease Name Howell Well No. 1 "A"
Office Address Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-4 19 55
Application for plugging filed 4-4 19 55
Application for plugging approved 4-4 19 55
Plugging commenced 4-5 19 55
Plugging completed 4-5 19 55
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5018 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	444	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug set at 400' with 20 sacks cement and 1/3 sack hulls.
Second plug set at 40 feet with 10 sacks cement and 1/3 sack hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Schafer Drilling Co.
Address Box 350, Pratt, Kansas

STATE OF Kansas, COUNTY OF Pratt, ss.
James E. Selby (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Pratt, Kas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of April, 19 55
Maudie B McBride
Notary Public.

My commission expires June 30, 1955

PLUGGING
FILE SEC 11 29 16w
BOOK PAGE 109 LINE 25

RECEIVED
APR - 6 1955
4-6-1955
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

HOWELL #1 "A"

KIOWA COUNTY KS.

0-60	Clay
60-150	Shale and Redbed
150-410	
410-550	Shale and Shells
550-950	Red Bed and Shells
950-970	Anhydrite
970-1365	Shale, Shells and Red Bed
1365-1650	Shale and Shells
1650-2170	Lime and Shale
2170-2290	Lime
2290-2715	Shale and Lime
2715-2790	Shale and Shells
2790-2840	Lime and Shale
2840-2895	Shale and Shells
2895-3400	Lime and Shale
3400-3475	Shale and Lime Shell
3475-4145	Lime and Shale
4145-4662	Lime
4662-4699	Coring
4699-4729	Shale and Lime
4729-4748	Viola
4748-4805	Lime
4805-4859	Chert and Lime
4859-4999	Lime
4909-4995	Sand & Lime
4995-5018	Lime
5018	TOTAL DEPTH

I certify that the above drillers log is true and correct as taken directly from the daily drilling reports of the #1 Howell "A".

E. Selby
Schaefer Drilling Co.

State of Kansas: County of Pratt: SS

The above ~~is~~ was subscribed and sworn to before me this 5th day of April, 1955.

Manda B. McBride
Notary Public

My commission expires June 30, 1955.

RECEIVED
STATE OF KANSAS
APR 5 1955
NOTARY PUBLIC

PLUGGING
FILE SEC 11 T 29 R (ka)
BOOK PAGE 109 LINE 25