

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County. Sec. 11 Twp. 29 Rge. 13  W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NW NW


Lease Owner Sohio Petroleum Company  
Lease Name Fincham Well No. 1  
Office Address P.O. Box 30, Casper, Wyoming  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole - Moved due to loss of circulation  
Date Well completed - - 19- -  
Application for plugging filed Verbal 5-29 1981  
Application for plugging approved Verbal 5-29 1981  
Plugging commenced - - 6-1 1981  
Plugging completed - - 6-2 1981

Reason for abandonment of well or producing formation  
Lost Circulation  
If a producing well is abandoned, date of last production  
N/A 19- -

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation N/A Depth to top - Bottom - Total Depth of Well 1205'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water	0	524	8-5/8"	524	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from - - feet to - - feet for each plug set.

Sanded from 1205' to 700' w/pea gravel - checked top of sand with wireline @ 700'.  
Dumped 7 yds redi-mix concrete in well from 700' to 0'. Let well set 1 day and  
finished filling w/redi-mix concrete. Cut csg 3' below ground level & welded on  
 $\frac{1}{2}$ " steel plate.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor - - - - -

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 15 1981  
CONSERVATION DIVISION  
Wichita, Kansas  
6-15-1981

STATE OF - - - - - COUNTY OF - - - - -  
(employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. R. Holcomb  
P.O. Box 30, Casper, WY 82602  
(Address)

SUBSCRIBED AND SWORN TO before me this 11<sup>th</sup> day of June, 1981

DEBRA J. WILSON - Notary Public  
County of Natrona State of Wyoming  
My Commission Expires Mar. 12, 1984

Debra J. Wilson  
Notary Public.

My commission expires

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

Fincham #1  
C-NW-NW Sec 11-29S-13W  
Pratt County Kansas

Commenced: 5-22-81

Completed: 5-29-81

OPERATOR: SOHIO PETROLEUM CO.

Depth		Formation	Remarks
From	To		
0	40	Surface Clay	Ran 13 jts of 23# 8 5/8" csg set @ 519' Cemented w/325 sks 60/40 Posmix 2% Gel - 3% CC - 50 sks Class A - 3% CC PD @ 2:30 a.m. 5-23-81
40	525	Sand-Clay	
525	1205	Redbed	
	1205 - TD		

SKID

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.


GABBERT-JONES, INC.

  
JAMES S. SUTTON II

Subscribed and sworn to before me this 23rd day of June, 1981.

  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.



RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1981  
CONSERVATION DIVISION  
Wichita, Kansas