

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 10 TWP. 29S RGE. 13 XE/W  
Location as in quarters or footage from lines:  
NE SE


Lease Owner Sohio Petroleum Co.  
Lease Name D. Fincham Well No. #2  
Office Address 50 Penn Place - Suite 1100 Oklahoma City, OK. 73118  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry  
Date Well Completed 6-3-83  
Application for plugging filed 6-3-83  
Plugging commenced 6-3-83  
Plugging completed 6-3-83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4787'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	546'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- Mud to 4300', Spot 50 sx. cement thru drill pipe.
- Mud to 960', Spot 40 sx. cement thru drill pipe.
- Mud to 570', Spot 40 sx. cement thru drill pipe.
- Mud to 40', Spot 10 sx. cement thru drill pipe.
- Spot 10 sx. cement in rathole.
- Spot 5 sx. cement in waterwell.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor White & Ellis Drilling, Inc.  
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Ernest Sifford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Ernest Sifford*  
401 E. Douglas #500 Wichita,  
(Address) Ks. 67202

SUBSCRIBED AND SWORN TO before me this 15<sup>th</sup> day of June, 1983


My Commission expires:



*Carolyn J. Tjaden*  
Notary Public.

JUN 16 1983

CONSERVATION DIVISION  
Wichita, Kansas



# WHITE

ANDELLIS DRILLING, Inc.

## DRILLERS LOG

OPERATOR: Sohio Petroleum 50 Penn Place - Suite 1100 Oklahoma City, OK. 73118

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,  
Wichita, Ks. 67202

Lease Name D. Fincham Well No. #2

Sec. 10 T. 29S R. 13W Spot NE SE

County Pratt State Kansas Elevation \_\_\_\_\_

### Casing Record:

Surface: 8 5/8" @ 546' with 425 sx. 2%gel  
3%cc

Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ sx.

Type Well: D & A Total Depth 4787'

Drilling Commenced 5-25-83 Drilling Completed 6-3-83

Formation	From	To	Tops
Cellar	0	7	Viola 4494
Shale, Lime	7	2000	Simpson 4625
Lime, Shale	2000	4625	Arbuckle 4725
Sand	4625	4705	
Lime	4705	4787	

RECEIVED  
STATE CORPORATION COMMISSION

JUN 16 1983

CONSERVATION DIVISION  
Wichita, Kansas