

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 8 TWP. 29S RGE. 13W E/W
Location as in quarters or footage from lines:
NW NW NW

Lease Owner Ronald Russ Prater, Inc.
Lease Name Barbee Well No. 1
Office Address 240 N. Rock Road - Suite 235, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole 67206
Date Well Completed March 4, 1981
Application for plugging filed Verbal Application
Plugging commenced March 4, 1981
Plugging completed March 4, 1981
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Pratt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. Leslie
Producing formation _____ Depth to top _____ bottom _____ T.D. 4,710'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	311'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,710 ft. (rotary total depth) to 1,140 ft. Set plug at 1,140 ft. and cemented with 40 sacks cement.
Filled hole with heavy rotary mud from 1,140 ft. to 300 ft. Set plug at 300 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 9 sacks cement in rat hole and 1 sack cement in water well.

Plugging operations accomplished utilizing Dowell Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell Div., Dow Chemical Co.
Hwy. 281 & Santa Fe, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Sedgwick, ss.

Dean Britting, Agent (~~employee of owner~~) ~~xxx (owner) xxx operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water-Suite 10, Wichita, KS
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 81

Elsie Willison
Elsie Willison - Notary Public.

My Commission expires: July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION
3-19-1981
MAR 19 1981

CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Ronald Russ Prater, Inc.

BCC. 8 T. 29S_R. 13W
 LOC. NW NW NW

FARM Barbee NO. 1

COUNTY Pratt

ROTARY TOTAL DEPTH 4,710'
 COMM. February 23, 1981 COMP. March 4, 1981
 CONTRACTOR H-30, INC. (Rig #3)
 ISSUED March 16, 1981

CASING

10 3/4"
 8 5/8" Set at 311' cemented w/275 sxs cement
 5 1/2"
 4 1/2"

ELEVATION 1,954' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	40'
Sand and Red Bed	312'
Red Bed and Shale	1,843'
Shale and Lime	2,014'
Lime and Shale	2,135'
Shale and Lime	2,367'
Lime and Shale	4,710'
Rotary Total Depth	4,710'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by drilling reports.


H-30, INC.



 Dean Britting

State of Kansas)
) ss:
 County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 16th day of March, 1981.



 Elsie Willison - Notary Public

My Commission Expires:
 July 25, 1982

RECEIVED
 CORPORATION COMMISSION
 MAR 19 1981
 CONSERVATION DIVISION
 Wichita, Kansas