

15-151-00443-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pratt

County. Sec. 8

Twp. 29S

Rge. 13W (E)

(W)

NORTH

Location as "NE/CNW/SW" or footage from lines

NW SE NW

Lease Owner Imperial Oil Company

Lease Name Garrison

Well No. 1

Office Address 780 Fourth Natl. Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole)

Dry hole

Date well completed

9/15/62

19

Application for plugging filed

9/15/62

19

Application for plugging approved

9/15/62

19

Plugging commenced

9/15/62

19

Plugging completed

9/15/62

19

Reason for abandonment of well or producing formation

No commercial quantities of oil found

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justus

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4909 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing	8-5/8" at 788'		not pulled			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 250' with 25 sacks cement

Set top plug at 40' with 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

SEP 27 1962

CONSERVATION DIVISION  
WICHITA, KANSAS

9-27-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address Box 97, Wakeeney, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John Lehman

(employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

John Lehman  
780 Fourth Natl. Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 1962

Bette J. Silcott  
Bette J. Silcott

Notary Public.

My commission expires July 5, 1966



DRILLER'S LOG

**RECEIVED**  
STATE CORPORATION COMMISSION

Imperial Oil Company  
780 Fourth National Building  
Wichita, Kansas

SEP 27 1962

CONSERVATION DIVISION

GARRISON NO. 1  
NW SE NW Sec. 8-29S-13W  
Pratt County, Kansas

Total Depth: 4909'

Commenced: 8/29/62 Completed 9/15/62

Elevation: 1943 K.B.  
Production: Dry

Contractor: Imperial Oil of Kansas, Inc.  
Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 788' with 375 sacks cement

Figures indicate bottom of formations:

		<u>TOPS</u>	
Surface Sand, Red Bed & Shale	580'	T/Anhydrite	782 (#1161)
Shale & Red Bed	782'	Heebner	3855 (-1912)
Anhydrite	788'	Toronto	3876 (-1933)
Shale & Shells	1965'	Douglas	3900 (-1957)
Shale & Lime	2155'	Brown Lime	4041 (-2098)
Lime	2380'	T/Lansing	4054 (-2111)
Lime & Shale	2550'	Base/Kansas City	4463 (-2520)
Lime	2925'	Mississippi	4520 (-2577)
Lime & Shale	3805'	Viola	4665 (-2722)
Lime	4587'	Rotary Total Depth	4909 (-2966)
Lime & Shale	4609'		
Lime	4645'		
Lime & Chert	4822'		
Lime	4851'		
Lime & Chert	4909'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

*Raymond R. Dombaugh*  
Raymond R. Dombaugh

Subscribed and sworn to before me this 24th day of September, 1962.  
My Commission Expires

July 5, 1966

*Bette J. Silcott*  
Bette J. Silcott, Notary Public