

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County. Sec. 7 Twp. 29S Rge. (E) 13 (W)  
Location as "NE/CNW/SW" or footage from lines NW SE  
Lease Owner William Gruenerwald & Associates, Inc.  
Lease Name Haskins Well No. 1  
Office Address P. O. Box 909, Colorado Springs, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 28 1967  
Application for plugging filed October 28 1967  
Application for plugging approved October 28 1967  
Plugging commenced October 28 1967  
Plugging completed October 28 1967  
Reason for abandonment of well or producing formation No producible shows

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	820'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 300', 1 sx dry cement, 1/2 sx hulls and 24 sx cement; heavy mud to 40', 1 sx dry cement, 1/2 sx hulls, plug, 9 sx cement. Plug down 7:10 AM, 10-28-68.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 14 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Garvey Drilling Company  
Address Route 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
A. G. Radke (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Garvey Drilling Company, Route 2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 1968  
[Signature]  
Notary Public.

My commission expires November 5th, 1969

# WELL LOG

COMPANY **William Gruenerwald & Associates, Inc.**

SEC. 7 T. 29S R. 13W

FARM **Haskins**

NO. **1**

LOC. **NW SE**

TOTAL DEPTH **4651'**

COUNTY **Pratt**

COMM. **10-16-67**

COMP. **10-28-67**

CONTRACTOR **Garvey Drilling Company**

CASING **8 5/8" @ 820' w/400 SK**


ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

40' Sand and Shale  
620' Red Bed with Sand Streaks  
799' Red Bed and Shale  
847' Anhydrite  
1695' Shale  
2070' Shale with Lime  
3250' Lime and Shale  
3600' Shale with Lime  
3820' Lime and Shale  
3957' Lime and Shale with Chalk Streaks  
4007' Lime and Shale  
4276' Lime  
4295' Lime and Shale  
4459' Lime  
4570' Lime and Chert  
4600' Chert, Dolomite and Sand  
4648' Sand and Chert  
4651' Sand  
4651' Sand RTD

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 14 1968  
CONSERVATION DIVISION  
Wichita, Kansas

State of **Kansas**

County of **Barton**

I, **Sam N. Stephens**

of **Garvey Drilling Company**

**Haskins No. 1**

upon oath state the above and foregoing is a true and correct copy of the log of the \_\_\_\_\_ well.

Subscribed and sworn to before me this **8th** day of **November** 19**67**

My Commission Expires: **November 5th, 1969**

**Richard Doy**  
NOTARY PUBLIC