

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

PRATT County, Sec. 7 Twp. 29S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW

Lease Owner Barnett Oil Company

Lease Name Bass Well No. 1

Office Address 417 First National Bank Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-22-63 19

Application for plugging filed 3-22-63 19

Application for plugging approved 3-22-63 19

Plugging commenced 3-22-63 19

Plugging completed 3-22-63 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Herman E. Justus, Nickerson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	840	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud to 270', 1/2 sack hulls & Plug @ 270' w/20 sx. cement
Heavy mud to 40', 1/2 sack hulls & Plug @ 40' w/10 sx. cement

RECEIVED
STATE CORPORATION COMMISSION

APR 4 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
H.L. Wilson of K & E Drilling, Inc., (employee or owner) or (owner or operator) of the above described well

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. L. Wilson
719 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of March, 19 63

My commission expires August 30, 1965 (Julene M. Bannon) Notary Public.



DRILLER'S WELL LOG

OPERATOR: Barnett Oil Company
417 First National Bank Building
Wichita 2, Kansas

WELL NAME: #1 Bass
LOCATION: SW NW NW, Sec. 7-29S-13W
Pratt County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: 3-8-63

CASING RECORD: 8-5/8" @ 840' w/400 sx.

COMPLETED: 3-22-63

ELEVATION: 1974 K.B.

ROTARY TOTAL DEPTH: 4700'

PRODUCTION: Dry Hole

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Clay	40
Sand	240
Red Bed	315
Shale & Red Bed	505
Shale	810
Anhydrite	865
Shale & Shells	2060
Shale & Lime	2355
Lime	2525
Shale & Lime	2795
Lime	3740
Shale & Sand	3895
Lime	4489
Lime & Chert	4528
Lime	4589
Shale	4620
Lime	4700 T.D.

RECEIVED
STATE CORPORATION COMMISSION

APR 4 1963

CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

H. L. Wilson
H. L. Wilson

Subscribed and sworn to before me this 25th day of March, 1963.

Julene M. Bannon
Julene M. Bannon) Notary Public.

My Commission expires: August 30, 1965

