

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-097-20,646
 LEASE NAME PRICE
 WELL NUMBER T

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR CROSS BAR PETROLEUM, INC.
 ADDRESS 220 W. DOUGLAS #140 WICHITA, KS.
67202
 PHONE # (316) 265-2279 OPERATORS LICENSE NO. 4243

4620 Ft. from S Section Line
4660 Ft. from E Section Line
 SEC. 22 TWP. 28 RGE. 20 (X) or (W)

Character of Well OIL
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

COUNTY KIOWA
 Date Well Completed _____
 Plugging Commenced 6-22-93
7-7-93

The plugging proposal was approved on 7-2-93
 by BARSTOW - DODGE CITY

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 12 1993
 (KCC District Agent's Name).
 CONSERVATION DIVISION
 Wichita, Kansas 7-12-1993

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____
P.B.T.D. 4360 T.D. 5184

Show depth and thickness of all water, oil and gas formations. PERFS: 4923-49
4334-44


Formation	Content	From	To	Size	Put In	Pulled out
		<u>0</u>	<u>325</u>	<u>8 5/8</u>	<u>325</u>	<u>0</u>
		<u>0</u>	<u>5184</u>	<u>6 1/2</u>	<u>5184</u>	<u>2920 FT. - 90TTS.</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
LAYED DOWN RODS + T.B.G. DUMPED SAND TO 4240'. DUMPED 55X CEMENT ON TOP OF SAND. 7-7-93: ALLIED TOP HOLE PLUGGED WITH 300# HULLS - 10 SK. GEL - 50 SK CEMENT - 100# HULLS - 8 5/8 PLUG - 150 SK. 60-40 PDZ - 6% GEL. 300# MAX - 150# ISI P.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. license No. 5893
 Address P.O. Box 847 - PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CROSS BAR PETROLEUM.
 STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY PLUGGING CONTRACTOR
 (Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Judy Berry
 (Address) 98 P.W.S. Inc.

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 93
Dorothy M. Furgason
 My Commission Expires: Feb 6, 1993 Notary Public