

15-097-00164-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County. Sec. 21 Twp. 28 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Beardmore Drilling Company

Lease Name Price "A" Well No. 1

Office Address 827 Beacon Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-4 19 59

Application for plugging filed 4-4 19 59

Application for plugging approved 4-4 19 59

Plugging commenced 4-4 19 59

Plugging completed 4-4 19 59

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 5045 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay		0'	50'			
Sand		50'	185'			
Shale & Shells		185'	305'	8-5/8"	305'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

0 to 35'	- 10 Sacks Cement
35'	- Wood Plug
35' to 180'	- Heavy Mud
180' to 240'	- 20 Sacks Cement
240'	- Wood Plug
240' to 5045'	- Heavy Mud

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1959

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company
Address 827 Beacon Building, Wichita, Kansas

4-18-1959

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Heber Beardmore (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Heber Beardmore

827 Beacon Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 19 59

Leonard P. Tolle

Leonard P. Tolle - Notary Public.

My commission expires January 28, 1960

PLUGGING
FILE SEC. 21 T. 28 R. 20
BOOK PAGE 30 LINE 43

15-097-06104-0000

BEARDMORE ET AL
#1 PRICE "A"
NE NE SW Section 21-28S-20W
Kiowa County, Kansas

Drilled By: Beardmore Drilling Company
Drilling Commenced: 3-17-59
Drilling Completed: 4-4-59

Casing Record: 8-5/8" set at 305' with 250 sacks cement on 3-17-59. Cement circulated.

Elevations: 2337 KB
2334 DF
2332 Gr

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Clay	50
Sand	185
Shale and Shells	305
Gray Shale	350
Red Bed	500
Anhydrite and Red Bed	575
Red Bed	750
Shale	1150
Red Bed and Shells	1330
Red Bed and Shale	1630
Shale and Lime	2560
Lime	2780
Lime and Shale	4070
Lime	4140
Shale and Lime	4217
Sand	4238
Shale and Lime	4250
Lime	5041
Rotary Total Depth	5041
Driller's Total Depth	5045

RECEIVED
STATE CORPORATION COMMISSION
APR 18 1959
CONSERVATION DIVISION
Wichita, Kansas

<u>SCHLUMBERGER TOPS</u>	<u>DEPTH</u>
Heebner	4168
Toronto	4190
Douglas	4248
Brown Lime	4328
Lansing	4338
Mississippian	4951
Mississippi Dolomite	4992

DST #1 4998-5028 Open 1 hr., weak blow. Recovered 145' muddy salt water. IBHP 1615 in 20 min., FBHP 1415 in 20 min., IF 35, FF 90.

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.



Subscribed and sworn to before me this 9th day of April, 1959.

Leonard P. Tolle
Leonard P. Tolle-Notary Public

My Commission Expires:
January 28, 1960

PLUGGING
FILE SEC. 21 T. 28 R. 20W
BOOK PAGE 30 LINE 43