


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 15 Twp. 28S Rge. 20 (X) (W)
Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Wm. Gruenerwald & Associates
Lease Name W. W. McDermet Well No. 1
Office Address P. O. Box 909, Colorado Springs, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-25-67 19__
Application for plugging filed 10-25-67 19__
Application for plugging approved 10-25-67 19__
Plugging commenced 10-25-67 19__
Plugging completed 10-25-67 19__
Reason for abandonment of well or producing formation commercial quantities of oil not found
If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5025 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	500'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 350' w/ 25 sacks
Top Plug @ 40' w/ 10 sacks
2 sacks - rathole

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.
Address 400 Insurance Building - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK
Robert F. Walters (employee of owner) or (owner or operator) or (contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters
400 Insurance Building - Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 67
Juanita M. Green
October 4, 1971 Notary Public.

15-097-20039-0000

DRILLER'S LOG

COMPANY: WM. GRUENERWALD & ASSOCIATES
P. O. BOX 909
COLORADO SPRINGS, COLORADO

WELL NAME: W. W. MC DERMET #1
C NW NW SEC. 15-28S-20W
KIOWA COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
400 INSURANCE BUILDING
WICHITA, KANSAS 67202

ROTARY DRILLING COMMENCED: OCTOBER 12, 1967
ROTARY DRILLING COMPLETED: OCTOBER 25, 1967

ELEVATION: 2315 KB

CASING RECORD: 8 5/8" set @ 500' w/ 275 sacks cement

LOG

0 - 70	Sand
70 - 320	Shale
320 - 500	Shale and Sand
500 - 515	Sand
515 - 1030	Red Bed
1030 - 1255	Red Bed, Shale and Shells
1255 - 1296	Anhydrite
1296 - 1441	Shale and Shells
1441 - 1735	Shale
1735 - 1825	Lime and Shale
1825 - 2210	Shale
2210 - 2330	Shale and Shells
2330 - 2378	Broken Lime
2378 - 2864	Lime and Shale
2864 - 3187	Shale and Lime
3187 - 3375	Shale and Shells
3375 - 3565	Shale and Lime Streaks
3565 - 4047	Shale and Lime
4047 - 4124	Shale
4124 - 4225	Shale and Lime
4225 - 4380	Lime and Shale
4380 - 4925	Lime
4925 - 4975	Core
4975 - 5025	Lime
5025	<u>Rotary Total Depth - D & A</u>

RECEIVED
STATE CONSERVATION COMMISSION
NOV 1 1967
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.
BY Robert F. Walters
ROBERT F. WALTERS, Partner

Subscribed and sworn to before me
this 31st day of October, 1967.
Juanita M. Green
Juanita M. Green, Notary Public
My Commission Expires: October 4, 1971
EDMICK CO