


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kiowa County, Sec. 15 Twp. 28 Rge. 20 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SE SE

Lease Owner Cherokee Resources, Inc.  
Lease Name Clayton Well No. 1  
Office Address 432 Mayo Building, Tulsa, Oklahoma 74103  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole  
Date Well completed 4/9/80 19  
Application for plugging filed 4/9/80 19  
Application for plugging approved 4/9/80 19  
Plugging commenced 4/9/80 19  
Plugging completed 12:30 p.m. 4/9/80 19  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation Depth to top Bottom Total Depth of Well  
Show depth and thickness of all water, oil and gas formations. RTD 4952'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	T.D.	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 600' with 50 sacks  
2nd plug @ 40' with 10 sacks  
5 sacks in rathole  
Job complete @ 12:30 p.m. 4/9/80

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc. 4-28-1980


STATE OF Kansas COUNTY OF Sedgwick, ss.  
James C. Remsberg of Slawson Drilling Co. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg  
James C. Remsberg  
200 Douglas Building, Wichita 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of April, 19 80

Mary Lou Taylor  
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



15-097-20596-0000

DRILLERS LOG

OPERATOR: Cherokee Resources, Inc.  
 432 Mayo Building  
 Tulsa, Oklahoma 74103

LEASE: Clayton #1  
 SE/4 SE/4 Sec. 15-28S-20W  
 Kiowa County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
 200 Douglas Building  
 Wichita, Kansas 67202

COMMENCED: 3/29/80

COMPLETED: 4/9/80

RTD: 4952'

SURFACE CASING: 8-5/8" set at 590 with 375 sx cement

0' to 515' Sand & Shale  
 515' to 593' Shale (12 1/4" Surf.Hole)  
 593' to 850' Sand & Shale  
 850' to 1610' Shale & Shells  
 1610' to 1695' Shale  
 1695' to 2105' Sand & Shale  
 2105' to 2405' Shale & Shells w/ Lime Stks.  
 2405' to 3385' Lime & Shale  
 3385' to 3700' Lime  
 3700' to 4300' Lime & Shale  
 4300' to 4720' Lime  
 4720' to 4777' Lime (Pawnee)  
 4777' to 4805' Lime  
 4805' to 4916' Lime & Shale  
 4916' to 4952' Mississippian  
 RTD 4952'

RECEIVED  
KANSAS COMMISSION

APR 23 1980

REGISTRATION DIVISION

STATE OF KANSAS  
 COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the Clayton #1 log for Cherokee Resources, Inc.

*James C. Remsberg*  
 James C. Remsberg

Subscribed and sworn to me this 24th day of April, 1980.

*Mary Lou Taylor*  
 Mary Lou Taylor, Notary

My commission expires January 17, 1981

