

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County. Sec. 25 Twp. 28 Rge. 15W (E) (W)

Location as "NE/CNWKSWK" or footage from lines NW/NW/SE

Lease Owner Bankoff Oil Company

Lease Name Johnson Well No. 1

Office Address 1312 Eisenhower Street, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19 _____

Application for plugging filed Yes 19 _____

Application for plugging approved Yes 19 _____

Plugging commenced 2-8 1957

Plugging completed 2-16 1957

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4838' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,518'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 4838'.
Plugging started 2-8-57. Finished 2-16-57.
Plugged off bottom with sand back to 4530' and dumped 5 sacks cement with bailer. Shot 5 1/2" casing at 3518'. Pulled pipe out of hole and plugged well with heavy mud to 300' and set permanent rock bridge. Dumped 20 sacks cement. Filled hole with mud to 35' and mixed 10 sacks for cap on well.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of February, 1957.

Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGGING
FILE SEC 25T 28 R 15W
BOOK PAGE 127 L 8 13

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1957
02-19-57
CONSERVATION DIVISION
Wichita, Kansas


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LEBEN DRILG.
Farm- Johnson No. 1

SEC. 25 T. 28 R. 15W
NW NW SE

Total Depth. 4838'
Comm. 12-22-55 Comp. 1-11-56
Shot or Treated.
Contractor. Leben Drilg. Co.
Issued. 11-10-56

County Pratt
KANSAS



CASING:
8 5/8" 382' w/300 sx cem.
5 1/2" 4730' w/100 sx cem.

Elevation. 2052' RB

Production. 80 BOPD & gas

Figures Indicate Bottom of Formations.

surface clay	60
sand-clay	160
shale-sand	280
red shale-sand	379
red shale-shells	500
shale-shells	1000
red bed-shells	1465
shale-shells	1740
shale-lime-shells	1975
shale-shells	2050
lime	2495
lime-shale	2610
lime	2710
lime-shale	3315
lime	3420
lime-shale	4095
lime	4495
Cherty Conglomerate	4517
Conglomerate-chert	4537
Mississippi	4556
lime-shale	4600
lime	4689
shale-lime	4701
Simpson	4748
shale-sand	4820
Arbuckle	4838

TOPS: Scout	
Anhydrite	857
Heebner	3880
Toronto	3908
Douglas	3927
Brown Lime	4037
Lansing	4063
B/Kansas City	4390
Mississippi	4537
Kinderhook	4551
Viola	4586
Simpson shale	4682
Simpson sand	4695
Arbuckle	4809

PLUGGING
FILE SEC 25 T 28 R 15 W
BOOK PAGE 137 LINE 13

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1957

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

No. 1 Cook "H"

CASING RECORD:	COMPANY:	Cities Service Company	DESCRIPTION:
8 5/8" @ 363' w/300 sx cement	CONTRACTOR:	Red Tiger Drilling Company	C NE/4 SW/4 Sec. 25-T28S-R15W Pratt County, Kansas
D & A	COMMENCED:	March 20, 1980	
TOTAL DEPTH: 3,600'	COMPLETED:	April 1, 1980	ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Surface Clay	0	370	
Shale	370	1205	
Red Bed, Shale & Shells	1205	1620	
Shale	1620	1880	
Lime & Shale	1880	2063	
Lime	2063	2210	
Shale & Lime	2210	2360	
Lime & Shale	2360	2945	
Lime	2945	2985	
Lime & Shale	2985	3280	
Lime	3280	3370	
Lime & Shale	3370	3600	
RTD		3600	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 10th day of April, 1980.

Joyce A. Hagermann
Notary Public

