

15-151-50013-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 24 Twp. 28S Rge. 15 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE/4 SE/4 NE/4

Lease Owner Twin Drilling, Inc.

Lease Name Berry Well No. 1

Office Address 1005 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 2-19 1958

Application for plugging filed 4-23 1960

Application for plugging approved 4-26 1960

Plugging commenced 5-8 1960

Plugging completed 5-8 1960

Reason for abandonment of well or producing formation

Insufficient production

If a producing well is abandoned, date of last production 9-30 1959

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4727 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	285.91	-
				5 1/2	4671.34	3903.75'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom hole plug.

Filled hole with gravel material and mud to bottom of surface. Set plug with 20 sacks cement

Filled hole to surface and set plug with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1960

CONSERVATION DIVISION
Wichita, Kansas

5-25-1960

Perf 4548-58 4 SPE
2 Boph

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H. S. Bennett
Address Route 2, Box 1, Mounds, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. R. Dunne (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. R. Dunne*

1005 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of May, 1960.

Almeda Day
Notary Public.

My commission expires September 9, 1961



WELL LOG

Well: Berry #1
 Commenced: January 21, 1958
 Completed: February 19, 1958

Location: SE SE NE
 Sec. 24-28S-15W
 Pratt County, Kansas
 Elevation: DF 2049
 Gr. 2047

Operator: Twin Drilling, Inc.
 1005 Central Building
 Wichita, Kansas
 Contractor: Same

Casing Record:

8 5/8" 285.91' W/200 sacks
 5 1/2" 4671.34' W/175 sacks

Sandy Clay	35	Lime	4690
Sand - Shale Streaks	195	(Dolomite 4687')	
Red Bed & Shale	281	Lime & Shale	4717
Shale & Shells	458	(Simpson Sand 4707')	
Shale - Shells Red Bed	905	Shale	4727 R.T.D.
Lime	1020		
Shale Lime	1175		
Shale	1775		
Lime & Shale	2055		
Lime	2300		
Lime & Shale	2345		
Lime W/Shale Breaks	2550		
Lime - Shale	2785		
Shale W/Lime Streaks	3041		
Lime - Shale	4067		
(Heebner 3885')			
(Br. Lime 4042')			
(Lansing 4058')			
(Kansas City 4396')			
Lime	4475		
Lime W/Shale Breaks	4525		
Lime	4550		
(Mississippi 4546')			
Chert & Lime	4558		
Lime	4575		
(Kinderhook 4571')			
Shale	4624		
Shale & Lime	4662		
(Viola 4649')			

Perforations:

Perforated 4 Holes per foot
 from 4548 - 4558. Initial
 production 2 barrels per hour.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 26 1960
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss.
 COUNTY OF SEDGWICK)

The undersigned, TWIN DRILLING, INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

TWIN DRILLING, INC.

By *Alameda Day*
 Secretary

Subscribed and sworn to before me
 this 28th day of February, 1958.

James S. Hicks
 Notary Public

My commission expires September 29, 1960.