

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

C-SW/4-SW/4-NE/4
COUNTY Pratt SEC. 22 TWP. 28 S RGE. 15 XE/W
Location as in quarters or footage from lines:

Lease Owner Spines Explor., Inc.
Lease Name Winklepleck Well No. 1
Office Address 530 4th Financial Center Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed API#15-151-21,124
Application for plugging filed Sept. 6, 1984
Plugging commenced Sept. 15, 1984
Plugging completed Sept. 19, 1984
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

Not economical to produce
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durant gave orders
Producing formation _____ Depth to top _____ bottom T.D. 4850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0		8 5/8		0
				5 1/2		2140'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 75 sx. of sand to 4250', 5 sx. of cement. Shot casing off at 2140'. recoverec
62 full joints of 5 1/2 casing.
PB TD 4790' Halliburton did top hole plugging: 300# cottonseed
Top perfs 4300' hulls-10 sx. gel-50 sx. cement-10 sx. gel- 100# hulls-
Btm. perfs 4642' pumped 125 sx. cement-S.I.P. 300#.

RECEIVED
STATE CORPORATION COMMISSION

OCT 22 1984


CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (employee of owner) or (~~owner or operator~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Judy Berry
Box 847 - Pratt, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October 19 84

Charlene M. Dudrey
Notary Public.

My Commission expires: 9/10/86