

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

Form CP-4
Rev. 12-15-80

JAN 25 1983

CONSERVATION DIVISION
Wichita Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt NE-NW-SE SEC. 22 TWP. 28S RGE. 15 X/W
Location as in quarters or footage from lines:

Locate Well
correctly on above
Section Platt.

Lease Owner Spines Exploration, Inc.
 Lease Name Frazier Well No. 1
 Office Address 530 4th Financial Center Wichita, Kansas
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 8-4-82
 Application for plugging filed 12-20-82
 Plugging commenced 1-10-83
 Plugging completed 1-13-83
 Reason for abandonment of well or producing formation Not economical to produce
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi Bob Parbutton
 Producing formation Kansas City Depth to top 4413 bottom 4416 T.D. 4810
 Show depth and thickness of all water, oil and gas formations. did not ever produce.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface pipe	fresh	0	420	8 5/8	420	0
Kansas City	gas/oil	0	4810	4 1/2	4810	3155'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


- CIBP 4480', set over perforations 4490-4500, perf. 4413-16'.
- Bull dog squeezed 1 sack hulls, 35 sacks common 2% gel, 3% CC, left 250' fillup.
- 1. Spotted 70 sacks, plug at 720', 5 Poz mix, 4% gel, 3% CC.
- 2. 40 sacks plug, 50/50 Poz mix, 4% gel, 3% CC Pushed wooden plug down to 40'.
- 3. 40' to surface, 10 sacks plug, 50/50 Poz mix, 4% gel, 3% CC.
- Shot pipe 3155', plug down 12:30, pumping rate 150#, ISIP -0.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc. Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Baird (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature)

Judy Baird
Box 847 - Pratt, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1983

Charlene M. Dudrey
Notary Public.

My Commission expires: 9/10/86