

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER <sup>15</sup>-151-21-486-00-00

LEASE NAME Frazier #1

WELL NUMBER #1

2310' Ft. from S Section Line

2310' Ft. from E Section Line

SEC. 22 TWP. 28S RGE. 15W EX (W)

COUNTY Pratt

Date Well Completed unknown

Plugging Commenced 12-5-85

Plugging Completed 12-10-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Brougher Oil Company

ADDRESS Box 1367, Great Bend, Kansas 67530

PHONE# (316) 793-5610 OPERATORS LICENSE NO. 6393

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Kinderhook Depth to Top 4574 Bottom 4580 T.D. 4857

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	461'	0
				5 1/2"	4849'	1943'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom plug was pumped with 70 sks 60-40-pos mix, plug stopped at 2094' found hole in casing, dumped 50' sand & 5 sks of cement cap, top plug used 3 sks of hulls, 10 gel, 50 sks of cement, 10 gel, 1 hull, 125 sks of cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Randy Wagner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Randy P Wagner

(Address) Box 768, Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 12 day of December, 1985

Carmen R. Cook  
Notary Public

My Commission Expires 12-12-86



STATE CORPORATION COMMISSION  
RECEIVED  
DEC 13 1985

CONSERVATION DIVISION  
Wichita, Kansas

12-13-1985