

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-151-00325-00-01

API NUMBER N/A  
DOCKET # D-19,770  
LEASE NAME BLACKWELDER  
WELL NUMBER #1 (SWD)

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2970 Ft. from S Section Line  
2310 Ft. from E Section Line  
SEC. 6 TWP. 29s RGE. 11 (X) or (W)  
COUNTY PRATT  
Date Well Completed 12/18/79  
Plugging Commenced 10/15/93  
Plugging Completed 10/15/93

LEASE OPERATOR WOODMAN-IANNITTI OIL COMPANY  
ADDRESS PO BOX 308; GREAT BEND KS 67530  
PHONE# (316) 792-1922 OPERATORS LICENSE NO. 6588  
Character of Well SWD  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 13, 1993 (date)  
by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom T.D. 4321/PB 3784'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	405'	8-5/8	405'	none
		0	3808'	2-7/8"	3808'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

Allied Cementing plugged w a total of 100 # HULLs 75 sax 60-40 Poz-Mx + 6% gel down the 2-7/8" tubing Max. Press-400#, SIP 0#. Then put 300# hulls +150 sax 60-40 Poz-Mix + 6% gel down annulus Max. Press-300# SIP 0#. Job completed @ 1:15 PM. Duane Rankin, KCC on location.


WOODMAN-IANNITTI OIL COMPANY & \_\_\_\_\_ 6588  
Name of Plugging Contractor Allied Cementing Co. Inc. License No. \_\_\_\_\_  
Address PO Box 31, Russell KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WOODMAN-IANNITTI OIL COMPANY  
STATE OF KANSAS COUNTY OF BARTON, ss.

D. J. Iannitti (~~Employee of Operator~~) or (Operator) c above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) WOODMAN-IANNITTI OIL COMPANY, PO BOX 308 CT. BEND, KS 67530

SUBSCRIBED AND SWORN TO before me this 21st day of October



Sharon K. Lingreen Notary Public  
May 12, 1996  
RECEIVED STATE CORPORATION COMMISSION OCT 25 1993 SHARON K. LINGREEN

USE ONLY ONE SIDE OF EACH FORM

Wichita, Kansas