

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
Wichita, Kansas

Rotary Drilling Commenced 2/12/59

LOCATION: SE SE NW, Sec. 35-29S-8W,
Kingman County, Kansas
Richardson A-2

Rotary Drilling Completed 2/27/59

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 250' (5 jts.) 8 5/8" 22.7# Armo Spiralweld Casing cemented with
125 sacks cement, 2% Gel. Cement circulated.

133 jts. of 4 1/2" 9.5# J-55 Smls. casing set at 4229' with 100 sacks cement.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing:)

Red Beds	340	Circ. for samples	4161
Shale & Lime	1340		4171
Lime	1905		4181
Lime & Shale	2535		4190
Shale	2740		
Shale & Lime	2870		
Lime	2945		
Shale	3070		
Lime & Shale	3175		
Lime	3272		
Lime & Shale	3403		
Lime	4181		
Mississippi	4188		
Lime	4230 T.D.		

S.L.M. at 2000 - OK
3000 - OK
4000 - OK

Slope Test at 2000 - 0° off
3000 - 0° off
4000 - 0° off

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1968
CONSERVATION DIVISION
Wichita, Kansas

10-31-68

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts
Attorney-in-Fact

STATE OF KANSAS, }
COUNTY OF SEDGWICK } ss.:

On this 10th day of March, 1959, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 13, 1962

Mary Ellen Sampson
Notary Public
(Mary Ellen Sampson)