

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

SMITH #1
 C SW SE SECTION 34-29S-19W
 KIOWA COUNTY, KANSAS

COMMENCED: OCTOBER 21, 1966
 COMPLETED: NOVEMBER 7, 1966

OPERATOR - BEARDMORE DRILLING COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	446	CLAY AND RED BED	
446	465	ANHYDRITE	
465	530	SAND	
530	598	SHALE AND SHELLS	RAN 29 JOINTS OF 8-5/8" CASING, SET @ 598' w/400 SACKS CEMENT.
598	985	SHALE AND SHELLS	
985	1246	RED BED AND SHALE	
1246	1278	ANHYDRITE	
1278	2230	SHALE	
2230	2660	SHALE AND LIME	
2660	3040	LIME	
3040	3845	LIME AND SHALE	
3845	4022	LIME	
4022	4470	LIME AND SHALE	
4470	4808	LIME	
4808	4881	LIME AND SHALE	
4881	4920	LIME	
4920	4933	LIME AND SHALE	
4933	5056	LIME	
5056	5071	CORE	
5071	5083	LIME	
5083	TD		RAN 159 JOINTS OF 4 1/2" CASING, SET @ 5077' w/100 SACKS CEMENT.

RECEIVED
 STATE CORPORATION COMMISSION

MAR 11 1970
 3-11-76
 CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SW SE SECTION 34-29S-19W, KIOWA COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 8TH DAY OF NOVEMBER, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My COMMISSION EXPIRES FEBRUARY 1, 1968.