

CONFIDENTIAL

Released  
1/15/81

1-195-20588

API No. 15 095 — 20588-0000  
County Number

S. 36 T. 29S R. 7W E  
W

Loc. C SE SE

Operator  
PICKRELL DRILLING COMPANY

County Kingman

640 Acres  
N

Address  
205 LITWIN BLDG., WICHITA, KS. 67202


Well No. 4 Lease Name COYKENDALL "A"

Footage Location  
feet from (N) (S) line feet from (E) (W) line

Principal Contractor PICKRELL DRILLING COMPANY Geologist Jay McNeil

Spud Date 5-27-77 Total Depth 4213 P.B.T.D.

Date Completed 6-28-77 Oil Purchaser Getty



Locate well correctly

Elev.: Gr. 1451

DF 1453 KB 1456

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface casing		8 5/8		201		170	
Prod. casing		4 1/2		4212		125	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	JSPF	4130-4140
TUBING RECORD			2	JSPF	4121-4130
Size	Setting depth	Packer set at			
2 3/8"	4154.64				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fracture w/250 gals., 15% NE Acid, 3000 gals. (72 bbls.) GSW pad,	
7500 gals. (178 1/2 bbls.) GSW w/5000# 20-40 sd. Flush w/3360 gals.	
(80 bbls.) GSW.	

INITIAL PRODUCTION

Date of first production 8-77	Producing method (flowing, pumping, gas lift, etc.) Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil 22 bbls.	Gas TSTM MCF	Water 85% bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

PICKRELL DRILLING COMPANY

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

OIL

Well No.

4

Lease Name

Coykendall "A"

S 36 T 29SR 7W E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Red Bed	0	206		
Shale	206	470		
Shale	470	1225		
Shale	1225	1401		
Lime & Shale	1401	1645		
Shale & Lime	1645	1820		
Lime	1820	2005		
Shale	2005	2210		
Lime & Shale	2210	2395		
Shale & Lime	2395	2590		
Shale & Lime	2590	2830		
Shale & Lime	2830	3030		
Lime & Shale	3030	3145		
Lime & Shale	3145	3320		
Lime & Shale	3320	3425		
Lime & Shale	3425	3520		
Lime	3520	3650		
Lime & Shale	3650	3745		
Lime & Shale	3745	3820		
Lime	3820	3900		
Lime & Shale	3900	3955		
Lime	3955	4025		
Lime & Shale	4025	4116		
Lime & Shale	4116	4128		
Lime	4128	4143		
Lime	4143	4213		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

C. W. Sebitts  
Partner

Signature

Title

12-6-77

Date