

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20845-6060

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name J. S. L. Petroleum Corp.

Complete Address 209 E. William, Wichita Kansas 67202

Lease Name Han Well No. 3

Location 100' E. C. NE NW Sec. 2 Twp. 28 Rge. 18<sup>W</sup> (East) (West)

County Kiowa Total Depth 5005'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abneromble Drilling Co.

Address 801 Union Center, Wichita Kansas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 8:00 PM Day: 3 Month: March Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

The anhydrite was topped at 1155'. They cement circulated 423' of 8 5/8" surface casing. 1st plug at 1130' with 60 bbl of cement. 2nd plug at 410' with 40 bbl of cement. 3rd plug 40' to 50' with 10 bbl of cement. Then circulated 10 bbl of cement in rat hole. Then plugged water well with 3 bbl of cement. The cement used was common with 2% gel + 3% C.C. The plugging was accomplished by Halliburton Co.

Amount of Surface Casing: 423' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luttie  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

3-9-1982

Signed: \_\_\_\_\_  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita Kansas

INVOICED

DATE 3-10-82

INV. NO. 9603-W